# **SIEMENS**

# VIDEOMED DI / DIM / DI-K

	AX
Repair Instructions	
F8 Fuse	
	© Siemens AG 1997 The reproduction, transmission or use of this document or its contents is not permitted without express written authority. Offenders will be liable for damages. All rights, including rights created by patent grant or registration of a utility model or design, are reserved.
Pagistor 5	English

Register 5

Print No.: RX52-022.091.01.02.02

Replaces: RX52-022.091.01.01.02

English

Doc. Gen. Date: 07.97

### **General Remarks**

The transfer resistance between the fuse cartridge and the holder can cause excess heating and to a failure.

In an error situation, Error 007 (AP-ID 16) is displayed; with the Lithostar Multiline:9020 on the control PC; with the Uroskop D1:Error 007 (AP-ID 10)

If there is a failure of the fuse cap with **one** contact terminals, replace the fuse cartridge with cap with a new version.

The new fuse cartridge (fuse cartridge) has two contact terminals with a bayonet design.

30 60 761

# **Components Affected**

- VIDEOMED DI / DIM / DI-K

## **Required Materials**

 Fuse block (with fuse cartridge)

# **Spare Parts**

- Melt fuse insert, 8 A 77 51 142

# **Required Tools**

- Standard service tool kit
- Soldering iron, 60 W
- Solder removal tool 20 49 708 RH 090
- Allen wrenches, M3 and M4

#### **Procedure**

#### **Observe ESD guidelines!**

- Switch the generator OFF.
- Switch the system breaker OFF.

### **Preparatory Worksteps**

- Disconnect all cables from the TV CCU.
- Remove the front shielding plate from the TV CCU.
- Remove the transformer unit;
   to this, only loosen the four mounting screws and pull out the unit.
- Remove the TV CCU.
- Remove the rear EMI shield.

#### Removing the Old Fuse Block

 Remove the solder from the 4 connector terminals for the F8 fuse block on the backplane board

Use the solder removal tool!

- Remove the fuse block from the backplane.
- Completely remove the solder from the soldering terminals with the solder removal tool.

#### Install the New Fuse Block

- Insert the new fuse block turned 45° into the adjacent diagonal holes.
- Solder in the connector terminals.
- Insert the new melt insert into the fuse cartridge.
- Insert the fuse cartridge with the melt insert into the fuse block.

#### **Final Work Steps**

- Reinstall the rear EMI shield.
- Insert the TV CCU in the cabinet and secure it in place.
- Insert the transformer unit and tighten the mounting screws.
- Install the front shielding plate.
- · Connect all cables.

#### **Function Check**

- Switch the system breaker ON.
- Switch the generator **ON**.
- After the system has been initialized, switch on fluoroscopy without an object in the beam path.
- At the generator, a tube voltage of less than 45 kV must stabilize when Automatic Fluoro Control is switched on.
- The fluoro image will appear on the monitor.
- Switch fluoroscopy OFF.

#### **Changes to Previous Version**

Page 1: Updated.

Page 2: Paragraph "General Remarks": Lithostar and Uroskop added.

Paragraph "Procedure" changed.

Page 4: "Final Work Steps" changed.

"Changes to Previous Version" added.

TD AX 4 / Link TD AX 1 / Biedermann / Tropia